

SECTION 1

DRAFT REPORT - TOWNSHEND DAM EXPLORATION PROGRAM

TOWNSHEND DAM

TOWNSHEND, VT

Contract No. DACW33-93-D-0004

Contracting/Ordering Officer:

Charles W. Coe

Delivery Order No. 0010

PREPARED FOR: U.S. Army Corps of Engineers
New England Division
424 Trapelo Road
Waltham, MA 02254-9149

PREPARED BY: Atlantic Testing Laboratories, Limited
P.O. Box 29
Canton, NY 13617

ATL REPORT NO. CD0047-1-9-94

OCTOBER 6, 1994

SECTION 2

TABLE OF CONTENTS

SECTION 2

TABLE OF CONTENTS

SECTION 1	Title Page
SECTION 2	Table of Contents
SECTION 3	Scope of Investigation <ul style="list-style-type: none">a. Delivery Orderb. Project Sitec. Purposed. Scope of Work
SECTION 4	Quality Control <ul style="list-style-type: none">a. General Certification Statementb. General Statementc. Records Takend. Equipment Usede. Procedures
SECTION 5	Summary of Activities and Telephone Logs <ul style="list-style-type: none">a. Summary of Activities - Table Ib. List of Telephone Logs - Table II
SECTION 6	Chain of Custody Log
SECTION 7	Safety Reports
SECTION 8	Field Inspector's Logs and Maps <ul style="list-style-type: none">a. Daily Log of Field Explorationsb. Boring Logsc. Figure 1 - General Project Location Mapd. Proposed Boring Locations - Plate No. 1e. Boring Location Plan
SECTION 9	Other Records Taken <ul style="list-style-type: none">a. Survey Notesb. Water Table Datac. Rock Coring Datad. Field Log of Test Boring (NED-121)

SECTION 3

SCOPE OF INVESTIGATION

a. Delivery Order No. 0010

(Contractor must submit four copies of Invoice)

CD 9/1/94

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0187), Washington, DC 20503. Please DO NOT RETURN your form to either of these addresses. Send your completed form to the procurement official identified in item 6.

1. CONTRACT/PURCH ORDER NO. DACW33-93-D-0004		2. DELIVERY ORDER NO. 0010		3. DATE OF ORDER. 08/29/94		4. REQUISITION/PURCH REQUEST NO. 961316-4229-0007		5. PRIORITY	
6. ISSUED BY DEPT. OF THE ARMY N. E. DIVISION, CORPS OF ENGRS 424 TRAPELO ROAD WALTHAM MA 02254-9149 Dorothy Maebius		CODE 961316		7. ADMINISTERED BY		CODE EMPTY		8. DELIVERY FOB [] DEST [X] OTHER (See Schedule)	
9. CONTRACTOR Vendor Id: 00001586		CODE 06KT9		FACILITY CODE		10. DELIVER TO FOB POINT BY 11/04/94		11. MARK IF BUS. IS [] SMALL [] SMALL DISADVANTAGED [] WOMEN-OWNED	
NAME AND ADDRESS ATLANTIC TESTING LAB, LIMITED P.O. BOX 29 CANTON NY 13617						12. DISCOUNT TERMS 0% 00 Days Net 030			
						13. MAIL INVOICES TO See Block 15			
14. SHIP TO GEOTECHNICAL ENGINEERING DIVISION, ENGINEERING DIRECTORATE AT ISSUING OFFICE		CODE GEB		15. PAYMENT WILL BE MADE BY FINANCE & ACCOUNTING OFFICER U.S.A. ENGR. DIV., NEW ENGLAND 424 TRAPELO ROAD WALTHAM MA 02254-9149		CODE FAO		MARK ALL PACKAGES AND PAPERS WITH CONTRACT OR ORDER NUMBER	
16. DELIVERY		X This delivery order is issued on another Government agency or in accordance with and subject to terms and conditions of above numbered contract.							
PURCHASE		Reference your furnish the following on terms specified herein.							
ACCEPTANCE. THE CONTRACTOR HEREBY ACCEPTS THE OFFER REPRESENTED BY THE NUMBERED PURCHASE ORDER AS IT MAY PREVIOUSLY HAVE BEEN OR IS NOW MODIFIED, SUBJECT TO ALL OF THE TERMS AND CONDITIONS SET FORTH, AND AGREES TO PERFORM THE SAME.									
NAME OF CONTRACTOR		SIGNATURE		TYPED NAME AND TITLE		DATE SIGNED			
If this box is marked, supplier must sign Acceptance and return the following number of copies:									
17. ACCOUNTING AND APPROPRIATION DATA/LOCAL USE 96X3123 CC1233410000000 (MC)						Award Oblig Amt US\$		34,481.00	
18. ITEM NO.	19. SCHEDULE OF SUPPLIES/SERVICE	20. QUANTITY ORDERED/ACCEPTED*	21. UNIT	22. UNIT PRICE	23. AMOUNT				
	FURNISH NECESSARY SUPPLIES AND SERVICES TO PERFORM BORINGS TO DEFINE THE CHARACTER OF SUBSURFACE MATERIALS AND TO DETERMINE THE DEPTH, CONTOUR AND QUALITY OF THE BEDROCK IN ACCORDANCE WITH THE ATTACHED SCOPE OF WORK AND DRAWINGS.								
*If quantity accepted by the Government is same as quantity ordered, indicate by x. If different, enter actual quantity accepted below quantity ordered and encircle.		24. UNITED STATES OF AMERICA <i>Charles W. Coe</i> BY: CHARLES W. COE 001		25. TOTAL \$ 34481.00		29. DIFFERENCES			
26. QUANTITY IN COLUMN 20 HAS BEEN [] INSPECTED [] RECEIVED [] ACCEPTED AND CONFORMS TO THE CONTRACT EXCEPT AS NOTED		27. SHIP. NO. [] PARTIAL [] FINAL		28. D.O. VOUCHER NO.		30. INITIALS			
DATE SIGNATURE OF AUTHORIZED GOVERNMENT REP.		31. PAYMENT [] COMPLETE [] PARTIAL [] FINAL		32. PAID BY		33. AMT VERIFIED CORRECT FOR			
36. I certify this account is correct and proper for payment						34. CHECK NUMBER			
DATE SIGNATURE AND TITLE OF CERTIFYING OFFICER						35. BILL OF LADING NO.			
37. REC'D AT	38. RECEIVED BY	39. DATE REC'D	40. TOTAL CONT.	41. S/R ACCOUNT NUMBER	42. S/R VOUCHER NO.				

ATLANTIC TESTING LAB, LIMITED

ITEM NO.	SCHEDULE OF SUPPLIES/SERVICE	QUANTITY	U/I	UNIT PRICE	AMOUNT
0126	GEOTECHNICAL INSPECTOR	128.00	HR	48.000000	6144.00
0128	PER DIEM - OVERNIGHT STAY	16.00	DA	55.000000	880.00
0129	MILEAGE FROM WALTHAM, MA AND RETURN	200.00	MI	0.500000	100.00
0130	GEOTECHNICAL SERVICES AND REPORT GEOTECHNICAL REPORT (PRICE EXPRESSED AS 50 PER CENT OF LINE ITEM 0001 OR 0003)	1.00	JB	3072.000000	3072.00
0131	SURVEYING MOBILIZATION AND DEMOBILIZATION	1.00	JB	450.000000	450.00
0133	MILEAGE FROM/TO CONTRACTOR'S EQUIPMENT STORAGE SITE(S). SITE(S) LOCATED IN	300.00	MI	0.500000	150.00
0134	SURVEY CREW AND EQUIPMENT	1.00	DA	880.000000	880.00
0136	DATA REDUCTION AND PLOTTING (PRICE EXPRESSED AS A PERCENTAGE OF LINE ITEM 0011).	1.00	JB	660.000000	660.00
0138	SAMPLE DELIVERY	1.00	JB	110.000000	110.00
0139	MOBILIZATION AND DEMOBILIZATION ONE DRILL RIG, CREW AND AUXILLARY EQUIPMENT MOBILIZATION AND DEMOBILIZATION	1.00	JB	1320.000000	1320.00
0141	MILEAGE FROM/TO CONTRACTOR'S MAIN EQUIPMENT STORAGE SITE. SITE LOCATED IN	300.00	MI	1.650000	495.00
0143	STANDBY TIME/ON SITE MOVES	32.00	HR	110.000000	3520.00

ATLANTIC TESTING LAB, LIMITED

ITEM NO.	SCHEDULE OF SUPPLIES/SERVICE	QUANTITY	U/I	UNIT PRICE	AMOUNT
166	DRIVE SAMPLE BORING WITHOUT CASING: CONTINUOUS SAMPLING 0-30 FT. DEPTH	80.00	LF	16.000000	1280.00
185	DRIVING AND PULLING CASING BX, NX SIZE	60.00	LF	18.000000	1080.00
187	6-INCH SIZE	20.00	LF	25.000000	500.00
205	NWX SIZE AND/OR NWM	80.00	LF	77.000000	6160.00
240	LUMBER FOR WORK PLATFORM OR SHORING	4.00	MB	1000.000000	4000.00
244	CRANE AND OPERATOR	32.00	HR	115.000000	3680.00

ATTACHMENT NO. 1

GED REQUISITION NO. 94-17

SCOPE OF WORK

PROJECT: Borings, Sampling and Rock Coring

SITE: Townshend Dam, Townshend, VT

PURPOSE: Perform borings to define the character of subsurface materials in the scour hole at the head of the outlet channel, and to determine the depth, contour and quality of the bedrock in the surrounding embankments. This information is required to design a system of post and timber lagging retaining walls and eliminate undermining of the outlet portal and erosion of the surrounding embankments.

1. SCOPE OF INVESTIGATIONS

a. **General.** Townshend Dam is located on the West River in Townshend, Vermont (see Plate Nos. 1 & 2). Subsurface explorations will consist of four (4) borings to be located on the surrounding outlet channel banks as shown on the attached Plan of Explorations (Plate No. 3). Some borings will require overburden sampling and all borings will require coring 20 feet into bedrock. Overburden is expected to range from 0 to 20 feet. Boreholes may be started with 6-inch diameter casing to allow progressive telescoping down to Nx-sized rock core. Continuous overburden sampling shall be conducted using a 3-inch I.D. solid spoon. It is assumed that boulders will be encountered at some of the borehole locations; boulders will be cored. Rock cores shall be Nx-sized. Boreholes shall be grouted upon completion of the hole.

b. **Inspection.** The Contractor shall provide one geologist or geotechnical engineer for field inspection during performance of the borings. The Contractor shall also provide sample jars and core boxes as required. It is possible that the Government will provide its own geologist or geotechnical engineer to perform the drilling inspection. If so, the Contractor will be informed of this decision along with the Notice to Proceed, and the Contractor will not be required to provide a field inspector and will not have to submit a comprehensive report as outlined in the Government contract. All samples shall be delivered by the Contractor to the U.S. Army Corps of Engineers, 424 Trapelo Rd., Bldg. 142, Waltham, MA, 02254-9149.

c. **Surveys.** Prior to drilling, boring locations will be located and marked by the Government. Upon completion of all holes, the Contractor shall provide a licensed surveyor to determine the coordinates (northings and eastings) and ground elevation at each borehole location. Local control points will be provided by the Government.

2. SITE CONDITIONS.

At Townshend Dam, drilling operations shall be on the surrounding outlet channel banks as shown on the attached plan and photographs. Drilling on steep slopes (up to 1 vertical on 1

horizontal) consisting of loose boulders, cobbles, and rockfill underlain by loose sands and gravels is required. The toes of the slopes are in water varying in depth to 12 feet. Discharge from the outlet channel conduit is expected to be about 100 cfs during drilling and stream velocities are expected to be about 5 to 10 fps. Access to the outlet channel area via an existing gravel road (see Plate 3) is available and will accommodate large construction equipment. However, access to some or all of the actual boring locations may require constructing timber platforms and/or utilizing tie off and anchoring methods (i.e. securing drill rig and platforms by using "deadmen" or heavy equipment and cables). Photographs of the existing site conditions are shown on Plates 4 through 7. These photos are provided to give the Contractor some indication of the existing access conditions but are not intended to fully represent all field conditions. Construction methods and drilling operations must ensure safe working condition and be in compliance with all safety standards referenced in the contract documents.

3. RIGHT-OF-ENTRY. Rights-of-Entry will not be required.

4. COORDINATION. The Government points of contact (POC's) are Steve Dunbar at (617) 647-8174 and Phillip Morrison, P.M. at (802) 365-7703 or 874-4881. The Government POC's shall be notified one week prior to the commencement of the work.

5. COMPLETION SCHEDULE. All work under this delivery order shall be completed within the following time limits:

Mobilization to Site: NLT 10 days after NTP

Complete Field Explorations: NLT 30 days after NTP

Submission of Draft Report: NLT 20 days after completion of explorations

Submission of Final Report: NLT 5 days after receipt of Government review comments

6. QUALITY CONTROL. The Contractor will be held responsible for all damages caused the government as a result of contractor negligence in the performance of any services furnished under the contract. Although submissions required by your contract are technically reviewed by the Government, it is emphasized that your work must be prosecuted using proper internal controls and review procedures. the letter of transmittal for each submission which you make shall include a certification that the submission has been subjected to your own review and coordination procedures to insure (a) completeness for each discipline commensurate with the level of effort, omissions, conflicts, and (c) the overall professional and technical accuracy of the submission. Documents which are deficient in any of these areas will be returned to you for correction and/or upgrading prior to our completing our review. Contract submission dates will not be extended if a resubmission of draft material is required for this reason.

7. Permits All necessary permits will be obtained by the Government.



↓ = approx
location
of prop.
boring.

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

CONNECTICUT RIVER FLOOD CONTROL

TOWNSHEND DAM
OUTLET CHANNEL
REPRESENTATIVE PHOTOS

D.S.S.
DESIGN BY
D.S.S.
DRAWN BY
T.L.B.
CHECK BY

WEST RIVER, VERMONT

GEOTECH. ENG. DIV.
PLATE NO. 4

SCALE: AS SHOWN
DATE:



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

CONNECTICUT RIVER FLOOD CONTROL

D.S.S.
DESIGN BY

D.S.S.
DRAWN BY

T.L.B.
CHECK BY

TOWNSHEND DAM
OUTLET CHANNEL
REPRESENTATIVE PHOTOS

WEST RIVER, VERMONT


GEOTECH. ENG. DIV.
PLATE NO. 5

SCALE: AS SHOWN
DATE:



General
View of Site
Looking
North

East Side
of Outlet
Works
Looking
Northwest



Access/Open
Area above
East Slope
Looking Northwest

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

S.W.D.
DESIGN BY
S.W.D.
DRAWN BY
M.A.V.
CHECK BY

TOWNSHEND SCOUR HOLE
SUPPLEMENTAL PHOTOGRAPHS
TAKEN JULY 5, 1994


GEOTECH. ENG. DIV.
PLATE NO. 6

SCALE: AS SHOWN
DATE: AUGUST 1994



East Slope
Looking
Southeast.

West Slope
Looking
West



West Side
of Outlet
& West Slope
Looking
North



↓ = approx.
location of
proposed
boring

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

S. W. D.

DESIGN BY

S. W. D.

DRAWN BY

M. A. V.

CHECK BY

TOWNSHEND SCOUR HOLE
SUPPLEMENTAL PHOTOGRAPHS
TAKEN JULY 5, 1994

GEOTECH. ENG. DIV.

PLATE NO. 7

SCALE: AS SHOWN

DATE: AUGUST 1994

b. Project Site

The project site is located on Townshend Dam in Townshend, Vermont.

c. Purpose

The purpose of the investigation was to define character of subsurface materials in the scour hole at the head of the outlet channel.

d. Scope of Work

Inspection and exploration instructions were provided by the Army Corps of Engineers (NED), in Delivery Order No. 0010 and are included in Section 3a. of this report. General inspection and exploration instructions were provided by the Army Corps of Engineers (NED) through the contracted Specifications for Services, and Equipment Necessary for Conducting Geotechnical Exploratory Work Various Locations in New England.

Drilling and sampling were performed by Atlantic Testing Laboratories, Limited's (ATL) personnel using ATL equipment. The test borings were sampled using a 2-1/2" I.D. split spoon sampler advanced with a 300-lb. safety hammer and a drop height of 18". The borings were advanced using NW casing by spinning and washing. Cores of the overburden and bedrock were obtained using a 2-1/2" I.D. NXM double tube core barrel.

The proposed scope of work required four test borings advanced from wooden platforms constructed on either side of the outlet channel scour hole on the rip-rap slopes. The borings were performed from September 20 through September 27, 1994.

ATL's surveyors provided locations and elevations for the test borings.

SECTION 4

QUALITY CONTROL

a. General Certification Statement

I hereby certify that the records, equipment, and procedures mentioned herein were used to perform the subsurface exploration. I also certify that the work was performed in a professional manner and meets the requirements set forth in the Delivery Order. This report has been subject to my review and is both complete and technically accurate.

CERTIFIED, October 6, 1994

Spencer F. Thew, P.E./L.S.

b. General Statement

The equipment and procedures used to perform the subsurface investigation are summarized below.

c. Records Taken

The "General Project Map", "Site Location Plan", and "Boring Location Plan" are included in Section 8.

Pertinent drilling procedures, sampling operations, and soil classification data were noted on the following forms provided by the Corps of Engineers:

NED 198	Daily Log of Field Explorations
NED 58 and 58a	Field Log of Test Boring
NED 121	Field Log of Test Boring
NED 59	Subsurface Water Observations
NED 130	Field Log of Test Boring in Rock

A series of logs for each of the borings is included in Section 8.

A summary of daily activities and a telephone log are Table I and Table II of Section 5, respectively. A chain of custody log is in Section 6. Safety meeting, reports, and NED Form 251 are in Section 7.

d. Equipment Used

Drilling equipment, survey equipment and supplies were provided by Atlantic Testing Laboratories, Limited (ATL). The subcontracted crane, with operator, was owned and operated by Miller Construction of Windsor, Vermont. A list of pertinent equipment follows:

1. Survey Equipment:

- 1 Topcon Electronic Theomat with single and triple reflectors

2. Drilling Equipment:

- CME-45C trailer-mounted drill rig
- NW size casing with spin shoes
- Drill rod, NW-threaded in 2 ft, 5 ft and 10 ft lengths used for sampling and advancing a roller bit
- 300-lb. safety hammer for driving split spoon samples
- 2 ft x 2-1/2" I.D. split spoon samplers
- 5 H.P. Honda sump pump with connecting hose and water holding tank
- NXM double tube size core barrels with diamond bits.

3. Subcontract Equipment:

- Link Belt 30-T Crane/Operator

e. Procedures

1. General Statement

A test boring investigation was performed on the rip-rap slopes of Townshend Dam outlet channel, Townshend, Vermont during the period September 19, 1994 through September 28, 1994.

2. Surveying Procedures

Atlantic Testing Laboratories, Limited's surveyors were on-site to determine the boring locations and elevations as drilled.

a. Horizontal and Vertical Control:

Stake out: Proposed boring locations were provided by the Corps of Engineers with flagged wooden stakes and/or fluorescent paint.

3. Boring Location Procedures

The coordinates and elevations for Townshend Dam control monuments were provided by the Corps of Engineers. Actual test boring locations and elevations were determined from angle/distance measurements from these monuments using the electronic theodolite and distomat.

e. Procedures (con't.)

4. Sampling and Drilling Procedures

Four borings were performed at Townshend Dam. The field exploration included drilling, soil sampling, and rock coring.

Soil sampling techniques involved retrieving material using the Standard Penetration Test. A 2-1/2" I.D. x 2 ft long split spoon sampler was advanced using a 300-lb. safety hammer. Samples were classified in the field in accordance with ASTM D-2488. Representative samples were taken from each soil sampling run and placed in 32-oz. jars with hermetically-sealed lids. Sample jars were labeled using a form similar to ENG Form 1742.

Overburden and bedrock was cored using a 5 ft long NXM double tube size core barrel and diamond bit. The rock core retrieved was placed in 5 ft long core boxes as specified in the contract. Bore holes were grouted upon completion of hole.

A Chain-of-Custody Log was maintained to document custody of samples between ATL and the USACE.

SECTION 5

SUMMARY OF ACTIVITIES

AND

CONVERSATION LOGS

a. SUMMARY OF ACTIVITIES
TABLE I

DATE

Monday,
September 19, 1994

ACTIVITY

5:00 pm - 6:00 pm, ATL Drill rig and 2 person drill crew (M. Hawkins, driller and C. Wheeler, helper), superintendent (P. Davis) and second helper (D. Hamilton) on site.
- Mobilized CME-45C drill rig, crew, and equipment to site. Unloaded drill rig trailer and equipment at Corps of Engineer's office at Townshend Dam.
- 6:00 pm departed site.

Tuesday,
September 20, 1994

6:00 am - 6:00 pm, ATL Drill rig and 2 person drill crew, superintendent, and second helper on site.

12:00 pm - 6:00 pm, Geotechnical Inspector (T. Wiggins) on site.

Crane and operator on site.

- Drill crew prepared rig for move to FD-D; moved drill tools and supplies to FD-D.
- 30-Ton Crane and operator picked drill rig from trailer and placed rig on location FD-D.
- P. Davis (ATL Superintendent) obtained keys from P. Morrison (CE-NED Site Representative), and permission to use telephone for job-related purposes.
- P. Davis and D. Hamilton (ATL Helper) constructed drilling platform at location FD-C. P. Davis purchased 1660 board feet of lumber and began construction of drilling platform at location FD-A.
- M. Hawkins (ATL driller) and C. Wheeler (ATL helper) sampled FD-D with 3" O.D. split spoon from 0' - 4'; destroyed sampler attempting sample from 4' - 6' on large boulder.
- Drill crew roller bitted through boulder to 5' and advanced NW casing to 5'; cored riprap overburden from 5' - 11' using NXM double tube core barrel; encountered bedrock at 11'. No soil present in overburden below 2'.
- Drill crew cored bedrock from 11' - 33' using double tube core barrel.
- T. Wiggins (ATL Geotechnical Inspector) contacted Y. Yatsevich (CE-NED) to report progress and schedule, and obtained permission to grout bore hole at end of day.
- Drill crew grouted bore hole at location FD-D and marked for surveyors.
- All personnel departed site at 6:00 pm; locking all gates.

a. SUMMARY OF ACTIVITIES (con't.)
TABLE I (con't.)

DATE

ACTIVITY

Wednesday,
September 21, 1994

6:00 am - 6:00 pm, ATL drill rig and 2 person drill crew, superintendent, second helper, and two geotechnical inspectors (T. Wiggins, and A. Brown) on site.
- Drill crew prepared rig for move with crane to location FD-C (standby for crane).
- Superintendent and helper completed construction of all three drilling platforms for locations FD-C, FD-A, and FD-B.
- 6:00 pm departed site.

Thursday,
September 22, 1994

6:00 am - 7:30 pm, ATL drill rig and 2 person drill crew, second helper, and geotechnical inspector (T. Wiggins) on site.
Crane and operator on site.
9:30 am - 2:30 pm, R. Schmidt (CE-NED Geologist) on site.
- Crane moved drill rig from location FD-D to FD-C.
- Drill crew cored bedrock with NXM double tube core barrel from 0' (surface in stream bottom) to 19' at location FD-C.
- R. Schmidt observed coring technique, rock core, and gave permission to grout the core hole at 19'.
- Drill crew grouted the core hole at location FD-C and prepared rig and equipment for move to FD-A.
- Crane moved drill rig from location FD-C to FD-A. Crew unbolted platform at location FD-C.
- Crane moved wooden platform from location FD-C to surface of dam. D. Hamilton disassembled platform.
- R. Schmidt and T. Wiggins located monumentation for survey work.
- Drill crew advanced boring at location FD-A by coring with NXM double tube core barrel and by rotary wash methods using NW casing and roller bits through 15' of rock overburden (rip-rap). Bedrock was cored using NXM double tube core barrel to 35'.
- 8:00 pm departed site.

Friday,
September 23, 1994

6:00 am -11:00 am, ATL drill rig and 2 person drill crew on site.
- Drill crew grouted bore hole at location FD-A and prepared rig and equipment for move to location FD-B.
- 11:00 am departed site.

a. SUMMARY OF ACTIVITIES (con't.)
TABLE I (con't.)

DATE

Monday,
September 26, 1994

ACTIVITY

11:00 pm -7:00 pm, ATL drill rig and 2 person drill crew (M. Hawkins driller; C. Wheeler, Helper), geotechnical inspector (A. Brown), and surveying crew.

Crane and operator on site.

- Surveyors mobilized to site to locate borings as placed.
- Moved drill rig with 30-T crane from FD-A to platform at FD-B. Advanced NXM double tube core barrel to 5'. No soil present in overburden. Roller bitted to 10'. Advanced NW casing to 11' and NXM core barrel to 14.5'. Drop encountered at 14.5' (overburden).
- Advanced NW casing to 17.5' and NXM core barrel from 16.5' to 21.5'. Bedrock encountered at 16.5'.
- 7:00 pm departed site.

Tuesday,
September 27, 1994

6:00 am - 6:00 pm, ATL drill rig and 2 person drill crew, and geotechnical inspector.

Crane and operator on site.

- Advanced NXM core barrel from 21.5' to 36.5' in bedrock. Grouted bore hole upon completion. Removed drill rig, platform and equipment with crane, and prepared for demobilization.
- A. Brown (ATL Geotechnical Inspector) contacted S. Dunbar (CE-NED) to report completion of project. Not available, left message.
- 6:00 pm departed site.

Wednesday,
September 28, 1994

6:00 am - 9:00 am, ATL drill rig and 2 person drill crew.

- Drill crew demobilized equipment from dam site, and performed project cleanup.
- Field work completed.
- 9:00 am departed site.

b. LIST OF TELEPHONE LOGS
TABLE II

<u>DATE</u>	<u>CONVERSATION</u>
Tuesday, September 13, 1994	<p>P. Davis (ATL) to S. Dunbar (CE-NED)</p> <ul style="list-style-type: none">- P. Davis stated startup time would be Monday, September 19, 1994. Start drilling on Wednesday, September 21, 1994, possibly Tuesday afternoon.- S. Dunbar requested P. Davis to call him back on Friday, September 16, 1994 to confirm times and requirements for ATL geotechnical inspector to be on site.
Friday, September 16, 1994	<p>P. Davis (ATL) to P. Morrison (CE-NED)</p> <ul style="list-style-type: none">- Reported mobilization on Monday, September 19, 1994. P. Morrison will give ATL keys to gates.- P. Davis told P. Morrison that lumber would arrive on Monday morning, September 19, 1994 and P. Morrison will try to be on site to receive lumber, and allow the truck driver to unload the lumber.
Friday, September 16, 1994	<p>P. Davis (ATL) to S. Dunbar (CE-NED)</p> <ul style="list-style-type: none">- Confirmed schedule of mobilization on Monday, September 19, 1994. Start drilling on Tuesday. This schedule met with S. Dunbar's approval. S. Dunbar stated Y. Yatsevitch and R. Schmidt (CE-NED) would be on site Wednesday, September 21, 1994.
Tuesday, 4:10 pm September 20, 1994	<p>T. Wiggins (ATL) to T. Petraska (Miller Construction)</p> <ul style="list-style-type: none">- Confirmed schedule for crane and operator for move from location FD-D to platform at FD-C. Crane will be on site Wednesday pm, September 21, 1994.
Tuesday, 3:50 pm September 20, 1994	<p>T. Wiggins (ATL) to Y. Yatsevitch (CE-NED)</p> <ul style="list-style-type: none">- Reported bedrock was encountered at 11' at FD-D and coring will be completed by end of day.- Described overburden as rip-rap (boulders with little or no soil present).- Obtained permission to grout bore hole upon completion of coring.- Y. Yatsevitch asked that ATL mark hole locations carefully for ATL surveyors.
Tuesday, 3:56 pm September 20, 1994	<p>T. Wiggins (ATL) to M. Remington (ATL)</p> <ul style="list-style-type: none">- Reported progress and schedule.

b. LIST OF TELEPHONE LOGS (con't.)
TABLE II

<u>DATE</u>	<u>CONVERSATION</u>
Wednesday, 7:15 am September 21, 1994	T. Wiggins (ATL) to Y. Yatsevitch (CE-NED) - Reported schedule for crane and operator in order to avoid a trip for CE-NED representatives, when ATL would not be coring. Y. Yatsevitch rescheduled site visit to Thursday, September 22, 1994. - Reported that rig on standby waiting for crane (expected pm today).
Thursday, 2:45 pm September 22, 1994	T. Wiggins (ATL) to M. Remington (ATL) - Reported drilling progress and schedule.
Tuesday, 12:00 pm September 27, 1994	A. Brown (ATL) to S. Thew and T. Wiggins (ATL) - Reported completion of FD-B (last of four borings), and beginning of demobilization from site. A. Brown (ATL) to S. Dunbar (CE-NED) - Reported completion of final boring. S. Dunbar was not in office, left message.
Friday, 3:05 pm September 30, 1994	A. Brown (ATL) to S. Dunbar (CE-NED) - Reported progress on draft report. Told him draft report and core samples should be to him by end of next week.

SECTION 6

CHAIN OF CUSTODY LOG

ENVIRONMENTAL LABORATORY
48 LAGRASSE STREET
WADDINGTON, NEW YORK 13694
315-388-4452, FAX 315-388-5510

THINK QUALITY

SECTION 7

SAFETY REPORTS

WEEKLY SAFETY MEETING

NEDSO

Date held 9/23/84

THRU: Area Engineer, _____ Area

Time 8:30 AM

TO: Safety Office, NED

1. Weekly safety meeting was held this date for the following personnel:

Contract No. _____ Contractor ATLConducted By T. Williams Personnel present (Contr) _____

(Sub) _____

Subjects discussed (Note, delete, or add): (Govt) _____

Individual Protective Equipment - other hats, beltsPrevention of Falls - safe harness, steel beams, use ropes, variousSafe Lifting Techniques - yesEmergency Communications - yesFire Prevention - N/ASanitation, First Aid - yesTripping Hazards - trash, hose, nails in lumber - yesStaging, Ladders, Concrete Forms - N/AHand Tools, Portable Power Tools, Woodworking Machinery - yesEquipment Maintenance (Zero defects) - yesHoisting Equipment - yesRopes, Hooks, Chains and Slings - yesElectrical Grounding, Temporary Wiring - yesLockouts for safe clearance procedures - electrical, pressure, moving part yesWelding - N/AExcavations - N/ALoose Rock and Steep Slopes - yesExplosives - N/AWater Safety - yesOther - nonePrepared by M. A. Higgins Title Asst. Eng.

2. Forwarded.

Signature _____
Resident EngineerCP: MANHOURS
Contractor 234.5
Sub Contractor 16.0
Period Covered 9/19/84 - 9/23/84
C-62

FIG No. 11

WEEKLY SAFETY MEETING

NEDSO

Date held 9/26/94 (mon)

THRU: Area Engineer, _____ Area

Time 12:30 PM

TO: Safety Office, NED

1. Weekly safety meeting was held this date for the following personnel:

Contract No. _____ Contractor Atlantic TestingConducted By A. Brown Personnel present (Contr) _____
(Sub) _____

Subjects discussed (Note, delete, or add): (Govt) _____

Individual Protective Equipment - Hardhats, Boots, Gloves

Prevention of Falls - Use Rope to Access Drill Platform

Safe Lifting Techniques - YesEmergency Communications - YesFire Prevention - YesSanitation, First Aid - YesTripping Hazards - trash, hose, nails in lumber - YesStaging, Ladders, Concrete Forms - YesHand Tools, Portable Power Tools, Woodworking Machinery - YesEquipment Maintenance (Zero defects) - YesHoisting Equipment - YesRopes, Hooks, Chains and Slings - YesElectrical Grounding, Temporary Wiring - Yes

Lockouts for safe clearance procedures - electrical, pressure, moving part

Welding - NAExcavations - NALoose Rock and Steep Slopes - Rope on Slope!Explosives - NAWater Safety - Yes

Other -

Prepared by [Signature] Title _____Geotechnical Eng.

2. Forwarded.

Signature _____

Resident Engineer

CP: MANHOURSContractor 20.0SubContractor 16.0Period Covered 9/24/94 - 9/28/94

C-62

FIG No. 11

SECTION 8

FIELD INSPECTOR'S LOGS AND MAPS

a. Daily Log of Field Explorations

NEW ENGLAND DIVISION
CORPS OF ENGINEERS, U.S. ARMY
WALTHAM, MASSACHUSETTS
FOUNDATIONS & MATERIALS BRANCH

LOG NO. 1DATE Monday, 9/19/94DAILY LOG OF FIELD EXPLORATIONSPROJECT TWOHEND DAMTEMPORARY ADDRESS Box 301 Wilder, VT 05098LOCATION WHERE CAN BE REACHED SamePHONE (802) 296 7213 TIME PmTEMPERATURE: MAX. 75°F MIN. 50°FWEATHER P. Cloudy

DRILLING TODAY

HOLE	AREA	FOOTAGE		FOOTAGE TODAY	MATERIAL
		FROM	TO		

TEST PITS OR AUGER BORINGS TODAY

HOLE	AREA	DEPTH	MATERIAL

HOLE	AREA	DEPTH	MATERIAL

PERSONNEL

NAME	HOURS
Paul Davis (superintendent)	12
Mark Hawkins (Driller)	12
Chris Wheeler (Drill Helper)	12
Don Hamilton (Drill Helper)	12

PLANT USED

ITEM	HOURS	BREAKDOWN HOURS
CME 45L Drill Rig	12	

T. Wiggins
CHIEF OF FIELD PARTY

FORM
DEC 63 198

REPLACES EDITION OF MAY 62 WHICH MAY BE USED UNTIL EXHAUSTED

(OVER)

NARRATIVE OF DAYS OPERATIONS

Mobilized Drill Rig/Crew from Canton, NY to project site unloaded Equipment at Dam Station House and secured it for the night.

Mobilized Lumber from ATL Warehouse,

MAN-HOUR WORK BREAKDOWN

[illegible]

WORK FOR TOMORROW

Set Drill Rig on location FD-D with crane and operator. Advance test boring to design Depth.
Construct Platform at location FD-L

FIELD PURCHASES

ITEM	AMOUNT
None	

ITEM	AMOUNT

NEW ENGLAND DIVISION
CORPS OF ENGINEERS, U.S. ARMY
WALTHAM, MASSACHUSETTS
FOUNDATIONS & MATERIALS BRANCH

LOG NO. 2DATE Sept 20, 1994

(Tues)

DAILY LOG OF FIELD EXPLORATIONSPROJECT Townshend Dam

TEMPORARY ADDRESS _____

LOCATION WHERE CAN BE REACHED _____

PHONE _____

TIME _____

TEMPERATURE: _____

MAX. 70MIN. 50WEATHER P. SunnyDRILLING TODAY

HOLE	AREA	FOOTAGE		FOOTAGE TODAY	MATERIAL
		FROM	TO		
PD-D	West Wall	0	33	33	Fill - Overburden, 1' to 33' - Bedrock

TEST PITS OR AUGER BORINGS TODAY

HOLE	AREA	DEPTH	MATERIAL

HOLE	AREA	DEPTH	MATERIAL

PERSONNEL

NAME	HOURS
Paul Davis (superintendent)	12
Mark Hawkins (Driller)	12
Chris Wheeler (Drill Helper)	12
Don Hamilton (Drill Helper)	12
Tom Wiggins (Geotech. Insp.)	6

PLANT USED

ITEM	HOURS	BREAKDOWN HOURS
CME 45C Drill Rig	12	
50 Ton crane w/oper.	8	

T. Wiggins

CHIEF OF FIELD PARTY

NED FORM
DEC 63 198

REPLACES EDITION OF MAY 62 WHICH MAY BE USED UNTIL EXHAUSTED

(OVER)

9/20/94
(Tue)

NARRATIVE OF DAYS OPERATIONS

Drill crew prepared rig for move to FD-D. 50 Ton Crane
picked rig from trailer and placed on location FD-D.
Drove split spoon from 0' to 4' where spoon was destroyed.
Roller Bitting from 0-5' and spun in NW casing to 5'.
Cored from 5' to 13.5' through overburden using NXM
Double Tube Core Barrel. Cored Bed at rock from 11'
to 33' using same. Spun NW casing to 13.5'.
Construction of Platform at FD-C began

MAN-HOUR WORK BREAKDOWN

*

NAME	MOS.	DEMOR.	MOVING	DRILL OVS.	DRILL BEDROCK	PREV. MAINT.	EQUIP. FAILURE	LOST TIME (WEATHER)	INSPECTION & SUPER.	MISC.	TOTAL
T. Wiggins									6		11
M. Hawkins			3	4	5						12
L. Wheeler			3	4	5						12
P. Davis										12	12
D. Hamilton										12	12

6

* Constructing Drill Platform at FD-C
WORK FOR TOMORROW

Move Rig to Location FD-C with crane + operator
complete construction of Drilling Platforms

FIELD PURCHASES

ITEM	AMOUNT
1660 BF. of Lumber	

ITEM	AMOUNT

NEW ENGLAND DIVISION
CORPS OF ENGINEERS, U.S. ARMY
WALTHAM, MASSACHUSETTS
FOUNDATIONS & MATERIALS BRANCH

LOG NO. 3DATE Wed 9-21-94DAILY LOG OF FIELD EXPLORATIONS

PROJECT TOWNSEND DAM
 TEMPORARY ADDRESS _____
 LOCATION WHERE CAN BE REACHED _____
 PHONE _____ TIME _____ TEMPERATURE: _____ MAX. 75 MIN. 50
 WEATHER Sunny

DRILLING TODAY

HOLE	AREA	FOOTAGE		FOOTAGE TODAY	MATERIAL
		FROM	TO		

TEST PITS OR AUGER BORINGS TODAY

HOLE	AREA	DEPTH	MATERIAL

HOLE	AREA	DEPTH	MATERIAL

PERSONNEL

NAME	HOURS
Paul Davis (Superintendent)	11.5
Mark Hawkins (Driller)	11.5
Chris Wheeler (Drill Helper)	11.5
Don Hamilton (Drill Helper)	11.5
Tom Wiggins (Geotech Insp.)	11.5
Alan Brown (Geotech Insp.)	11.0

PLANT USED

ITEM	HOURS	BREAKDOWN HOURS
CMC 45C	11.5	

T. Wiggins
CHIEF OF FIELD PARTY

FORM
NED DEC 63 198

REPLACES EDITION OF MAY 62 WHICH MAY BE USED UNTIL EXHAUSTED

(OVER)

9/21/94
(weds)

NARRATIVE OF DAYS OPERATIONS

Drilling crew on stand by waiting for crane to move from Drill rig to from FD-D to platform at FD-L. PREPARING Equipment for move.

Construction of platforms continues for FD-B and FD-A

MAN-HOUR WORK BREAKDOWN

NAME	MOB.	DEMOB.	MOVING	DRILL OVS.	DRILL BEDROCK	PREV. MAINT.	EQUIP. FAILURE	LOST TIME (WEATHER)	INSP. & SUPER.	MSC.	TOTAL
P. Davis										11.5	11.5
M. Hawkins			11.5								11.5
C. Wheeler			11.5								11.5
D. Hamilton										11.5	11.5
T. Wiggins			11.5							11.5	11.5
A. Brown			11.0								11.0

* CONSTRUCT PLATFORMS

** - STAND BY / MOVING

WORK FOR TOMORROW

Move Drill Rig from FD-D to FD-L and advance boring to specified depth.

FIELD PURCHASES

ITEM	AMOUNT

ITEM	AMOUNT

NEW ENGLAND DIVISION
CORPS OF ENGINEERS, U.S. ARMY
WALTHAM, MASSACHUSETTS
FOUNDATIONS & MATERIALS BRANCH

LOG NO.

4

DATE

THURSDAY 9/22/94

DAILY LOG OF FIELD EXPLORATIONS

PROJECT

TOWNSHEND DAM

TEMPORARY ADDRESS

LOCATION WHERE CAN BE REACHED

PHONE

TIME

TEMPERATURE:

MAX.

70

MIN.

55

WEATHER

CLOUDY

DRILLING TODAY

HOLE	AREA	FOOTAGE		FOOTAGE TODAY	MATERIAL
		FROM	TO		
FD-C	WEST WALL	0.0	19.0	19.0	BEDROCK
FD-A	EAST WALL	0.0	35.0	35.0	RIP-RAP OVERBURNED TO 15.0'; BEDROCK

TEST PITS OR AUGER BORINGS TODAY

HOLE	AREA	DEPTH	MATERIAL

HOLE	AREA	DEPTH	MATERIAL

PERSONNEL

NAME	HOURS
M. HAWKINS (DRILLER)	13.5
C. WHEELER (HELPER)	13.5
D. HAMILTON (HELPER)	13.5
T. WIGGINS (AED. INSP.)	13.5

PLANT USED

ITEM	HOURS	BREAKDOWN HOURS
CME ASC DRILL RIG	13.5	
LINK BELT CRANE w/OPER	8	

CHIEF OF FIELD PARTY

NED FORM
DEC 63 198

REPLACES EDITION OF MAY 62 WHICH MAY BE USED UNTIL EXHAUSTED

(OVER)

9/22/94
(Thurs)

NARRATIVE OF DAYS OPERATIONS

Crane moved drill rig from FD-D to FD-C. Advanced
borehole at FD-C to 19.0' - All Bedrock (No overburden) with
Grouted FD-C to Surface
Crane moved drill rig from FD-C to FD-A. Advanced
borehole at FD-A to 35.0' - R.O.-gap from 0 to 15' with
Bedrock from 15' to 35' with NXM Core.
Spun in NW casing to 15.5'
Construction of Platform at FD-B was completed.
Removal of Platform at FD-C began

NXM Core

NXM Core

MAN-HOUR WORK BREAKDOWN

NAME	MOB.	DEMGR.	MOVING	DRILL OVS.	DRILL BEDROCK	PREV. MAINT.	EQUIP. FAILURE	LOST TIME (WEATHER)	INSP. & SUPER.	* MISC.	TOTAL
M. KIRKINIS			2	2	9.5						13.6
C. WHEELER			2	2	9.5						13.6
D. HAMILTON										*13.5	
F. WICKINS			12M						13.5		13.5

*CONSTRUCTING/DISMANTLING PLATFORMS..

WORK FOR TOMORROW

Dismantle platform FD-C - Prepare drill rig for
move to FD-B

FIELD PURCHASES

ITEM	AMOUNT

ITEM	AMOUNT

NEW ENGLAND DIVISION
CORPS OF ENGINEERS, U.S. ARMY
WALTHAM, MASSACHUSETTS
FOUNDATIONS & MATERIALS BRANCH

LOG NO. 5DATE FRIDAY, 9/23/94DAILY LOG OF FIELD EXPLORATIONS

PROJECT TOWNSEND DAM
TEMPORARY ADDRESS _____
LOCATION WHERE CAN BE REACHED _____
PHONE _____ TIME _____ TEMPERATURE: _____ MAX. 60 MIN. 60
WEATHER RAIN

DRILLING TODAY

HOLE	AREA	FOOTAGE		FOOTAGE TODAY	MATERIAL
		FROM	TO		

TEST PITS OR AUGER BORINGS TODAY

HOLE	AREA	DEPTH	MATERIAL

HOLE	AREA	DEPTH	MATERIAL

PERSONNEL

NAME	HOURS
M. WANKINS (DRILLER)	5 1/2
C. WINTERLUR (HELPER)	5 1/2

PLANT USED

ITEM	HOURS	BREAKDOWN HOURS
CME 45C DRILL RIG	5 1/2	

CHIEF OF FIELD PARTY

FORM
DEC 63 198

REPLACES EDITION OF MAY 62 WHICH MAY BE USED UNTIL EXHAUSTED

(OVER)

NEW ENGLAND DIVISION
CORPS OF ENGINEERS, U.S. ARMY
WALTHAM, MASSACHUSETTS
FOUNDATIONS & MATERIALS BRANCH

LOG NO. 6DATE Monday 9/26/94DAILY LOG OF FIELD EXPLORATIONS

PROJECT Townshend Dam
TEMPORARY ADDRESS _____
LOCATION WHERE CAN BE REACHED _____
PHONE _____ TIME _____ TEMPERATURE: 68 MAX. _____ MIN. 55
WEATHER Cloudy

DRILLING TODAY

HOLE	AREA	FOOTAGE		FOOTAGE TODAY	MATERIAL
		FROM	TO		
FD-B	East Wall	0	21.5	21.5	Overburden and Bedrock

TEST PITS OR AUGER BORINGS TODAY

HOLE	AREA	DEPTH	MATERIAL

HOLE	AREA	DEPTH	MATERIAL

PERSONNEL

NAME	HOURS
A. Brown (Geot. Insp.)	8
M. Hawkins (Driller)	8
C. Wheeler (Drill Helper)	8
Survey Crew	

PLANT USED

ITEM	HOURS	BREAKDOWN HOURS
CME 45C Drill Rig	8	
Link Belt Crane/ Operator	8	

A. Brown
CHIEF OF FIELD PARTY

FORM
NED DEC 63 198

REPLACES EDITION OF MAY 62 WHICH MAY BE USED UNTIL EXHAUSTED

(OVER)

9/26/94
(Mon)

NARRATIVE OF DAYS OPERATIONS

Drill crew, crane/operator, survey crew and geotechnical inspector on site - Surveyed locations and elevations of all four borings. Crane moved drill rig from FD-A to FD-B and removed drilling platform at FD-A.
Advanced boring FD-B from 0' to 21.5'

MAN-HOUR WORK BREAKDOWN

NAME	MOB.	DEMOS.	MOVING	DRILL OVB.	DRILL BEDROCK	PREV. MAINT.	EQUIP. FAILURE	LOST TIME (WEATHER)	INSP. & SUPER.	MISC.	TOTAL
A. Brown									8		8
M. Hawkins			2	3	3						8
C. Wheeler			2	3	3						8
Survey crew											

WORK FOR TOMORROW

Continue boring FD-B and advance to specified depth. Remove drill rig from platform at FD-B and prepare for demobilization.

FIELD PURCHASES

ITEM	AMOUNT

ITEM	AMOUNT

NEW ENGLAND DIVISION
CORPS OF ENGINEERS, U.S. ARMY
WALTHAM, MASSACHUSETTS
FOUNDATIONS & MATERIALS BRANCH

LOG NO. 7DATE Tuesday 9/27/94DAILY LOG OF FIELD EXPLORATIONSPROJECT TOWNSHEND DAM

TEMPORARY ADDRESS _____

LOCATION WHERE CAN BE REACHED _____

PHONE _____ TIME _____ TEMPERATURE: _____ MAX. 65 MIN. 55WEATHER RAINDRILLING TODAY

HOLE	AREA	FOOTAGE		FOOTAGE TODAY	MATERIAL
		FROM	TO		
FD-B	East Wall	21.5	36.5	15	BEDROCK

TEST PITS OR AUGER BORINGS TODAY

HOLE	AREA	DEPTH	MATERIAL

HOLE	AREA	DEPTH	MATERIAL

PERSONNEL

NAME	HOURS
A. BROWN (GEOTECH. INS P.)	10
M. HAWKINS (DRILLER)	12
C. WHEELER (DRILL HELPER)	12

PLANT USED

ITEM	HOURS	BREAKDOWN HOURS
CME 45 C DRILL RIG	12	
LINK BELT CRANE	8	
OPERATOR		

T. Wiggins for A. Brown
CHIEF OF FIELD PARTY

NED FORM
DEC 63 198

REPLACES EDITION OF MAY 62 WHICH MAY BE USED UNTIL EXHAUSTED

(OVER)

NEW ENGLAND DIVISION
CORPS OF ENGINEERS, U.S. ARMY
WALTHAM, MASSACHUSETTS
FOUNDATIONS & MATERIALS BRANCH

LOG NO. 8DATE Wednesday 9/28/94DAILY LOG OF FIELD EXPLORATIONSPROJECT TOWNSEND DAM

TEMPORARY ADDRESS _____

LOCATION WHERE CAN BE REACHED _____

PHONE _____ TIME _____ TEMPERATURE: _____ MAX. 65 MIN. 55WEATHER LIGHT RAINDRILLING TODAY

HOLE	AREA	FOOTAGE		FOOTAGE TODAY	MATERIAL
		FROM	TO		

TEST PITS OR AUGER BORINGS TODAY

HOLE	AREA	DEPTH	MATERIAL

HOLE	AREA	DEPTH	MATERIAL

PERSONNEL

NAME	HOURS
M. HAWKINS (DRILLER)	11
C. WISSELER (HELPER)	11

PLANT USED

ITEM	HOURS	BREAKDOWN HOURS
CME 45C DRILL RIG	11	

CHIEF OF FIELD PARTYNED FORM
DEC 63 198

REPLACES EDITION OF MAY 62 WHICH MAY BE USED UNTIL EXHAUSTED

(OVER)

b. Boring Logs

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site TOWNSEND DAM Page 1 of 3 Pages

PD-94-X3
Boring No. FD-A Desig. FD-A Diam. (Casing) 3"

FIELD LOG OF TEST BORING

Co-ordinates: N 201255.60 E 446170.20

Elevation Top of Boring 460.23 M.S.L. Hammer Wt. _____ Boring Started 9/22/94
Total Overburden Drilled 15' Feet Hammer Drop _____ Boring Completed 9/22/94
Elevation Top of Rock 445.23 M.S.L. Casing Left _____
Total Rock Drilled 20 19.5 Feet Subsurface Water Date 451.43 Page SEE SEC. 9
Elevation Bottom of Boring 425.23 M.S.L. Obs. Well _____
Total Depth of Boring 35' Feet Drilled By Ma. Hawkins, C. Wheeler
Core Recovered 100 % No. Boxes 2 Mfg. Des. Drill GMB-456
Core Recovered 19.5 Ft. : _____ Diam. _____ In. Inspected By: T. Wiggins
Soil Samples NONE In. Diam. _____ No. Classification By: T. Wiggins
Soil Samples _____ In. Diam. _____ No. Classification By: _____

DEPTH	CORE/SAMPLE			BLOWS PER FT CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE	DEPTH RANGE			
1	OB-1	NXB	0		ADVANCED NXBA DOUBLE TUBE CORE BARREL THROUGH COBBLES AND BOULDERS	COBBLES, BOULDERS 42" Recovery (OVERBURDEN)
2						
3						
4						
5			5		ADVANCED NXBA DOUBLE TUBE CORE BARREL THROUGH COBBLES AND BOULDERS	COBBLES, BOULDERS 18" Recovery (OVERBURDEN)
6						
7						
8			8.5			
9					AFTER 2ND OVERBURDEN Run w/ NXBA CORE Barrel, Spun NW casing to 15.0'	
GENERAL REMARKS:						

DEPTH		CORE/SAMPLE		BLOWS PER FT	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
1"		NO.	SIZE	DEPTH CORE RANGE		
11					SPIN NW CASING TO 15.0' (Rotary Wash Boring)	Boulders, (RIP-RAP) COBBLES, ROCK FRAGMENTS (LOOSE OVERBURDEN TO 15.0')
12						
13						
14						
15					15.0' TOP OF BEDROCK	
16					Rotary Wash Boring	
17	R-1	NXM		15.5' 54" Rec.	15.0' TOP OF BEDROCK SPUN NW CASING TO 15.5'; THEN CLEANED W/ ROLLER BIT TO 15.5' ADVANCED NXM DOUBLE TUBE CORE BARREL TO 20.0' SAMPLED 15.5' TO 20.0'	BEDROCK GREY GNEISS 4 TOTAL PIECES 100% Recovery (54") RQD = 100%
18						
19						
20				20.0'		
21					ADVANCED NXM DOUBLE TUBE CORE BARREL TO 25.0'	BEDROCK GREY GNEISS 3 Pieces 100% Recovery RQD = 100%
22	R-2	NXM			SAMPLED 20.0' TO 25.0'	
23						
24						
25				25.0'		
26	R-3	NXM			ADVANCED NXM DOUBLE TUBE CORE BARREL TO 30.0' SAMPLED 25.0' TO 30.0'	BEDROCK GREY GNEISS 4 PIECES 100% Recovery RQD = 100%

NED 58A (Test)

Boring No. FD-A

DEPTH		CORE/SAMPLE		BLOW PER FT	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
1"		NO.	SIZE	DEPTH CORE RANGE		
	Run 3 (cont)					
29						
29						
30				30		
31		NXM			ADVANCED NXM DOUBLE TUBE CORE BARREL TO 35.0'	BEDROCK Grey Gneiss 4 Pieces 100% Recovery RAD=100%
32	Run 4				SAMPLED 30.0' to 35.0'	
33						
34						
35				35.0	EXPLORATION TERMINATED	9/22/94
					BOTTOM OF BORING 35.0' HOLE GROUTED W/CEMENT BENTONITE TO TOP OF HOLE	

ED 58A (Test)

Boring No. FDA

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site TOWSHEND DAM Page 1 of 3 pages

Boring No. FD94-X4 ~~FD-B~~ Desig. FD-B Diam. (Casing) 3" NW

FIELD LOG OF TEST BORING

Co-ordinates: N 201220.59 E 446186.35

Elevation Top of Boring 462.60 M.S.L. Hammer Wt. _____ Boring Started 9/26/94
Total Overburden Drilled 16.5 Feet Hammer Drop _____
Elevation Top of Rock 446.10 M.S.L. Casing Left No Boring Completed 9/27/94
Total Rock Drilled 20.0 Feet Subsurface Water Data 455.80 Page SEE SEC. 9
Elevation Bottom of Boring 426.10 M.S.L. Obs. Well _____
Total Depth of Boring 36.5' Feet Drilled By MA. HAWKINS, L. WHEELER
Core Recovered 95 % No. Boxes 2 Mfg. Des. Drill CME-45C
Core Recovered 19 Ft : _____ In. Inspected By: A. BROWN
Soil Samples NONE In. Diam. _____ No. Classification By: A. BROWN
Soil Samples _____ In. Diam. _____ No. Classification By: _____

DEPTH		CORE/SAMPLE			BLOWS PER FT CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	ft	NO.	SIZE	DEPTH RANGE			
	1	OB- 1	NX	0	17" Rec.	ADVANCED NXM CORE BARREL THROUGH COBBLES AND BOLDERS	COBBLES AND BOLDERS 17" RECOVERY (OVERBURDEN)
	2						
	3						
	4						
	5			5			
	6					ROLLER BITTED TO 10', SPUN NW CASING TO 11' (CONTACT WITH BORING)	COBBLES AND BOLDERS - VOIDS TO 12" (- OVERBURDEN)
	7						
	8						
	9						

GENERAL REMARKS:

DEPTH	CORE/SAMPLE			BLOWS PER FT	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	No.	SIZE	DEPTH RANGE			
11			11			
12			11		ADVANCED NXM DOUBLE TUBE CORE BARREL TO 16' THROUGH COBBLES AND BOWDERS	COBBLES AND BOWDERS 12" RECOVERY (OVERBURDEN)
13	OB-2	NXM		20% Rec.	SPUN NXM CASING TO 16.5'	(VOIDS TO 6" THICKNESS)
14						
15						
16			16			
			16		VOIDS (SPUN CASING)	
			16.5			
17			16.5		ADVANCED NXM DOUBLE TUBE CORE BARREL TO 21.5' (5.0')	BEDROCK - 90% RECOVERY, GREY GNEISS 4 PIECES
18	R-1	NXM		90% Rec.	SAMPLED 16.5' TO 21.5'	RQD = 100%
19					SPUN NXM CASING TO 17.5'	WEATHERED TO 17.5'
20						
21			26.5			
22					ADVANCED NXM DOUBLE TUBE CORE BARREL 5.0'	100% RECOVERY
23	R-2	NXM		100% Rec.	SAMPLED FROM 21.5' TO 26.5'	RQD = 93%, 6 PIECES
24						GREY GNEISS
25						
26						

9/27/94

DEPTH		CORE/SAMPLE		BLOWS PER FT	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	ft.	NO.	SIZE	DEPTH CORE RANGE		
				26.5		
	27	R-3	NXM		ADVANCED NXM Double TUBE CORE BARREL 5.0' SAMPLED FROM 26.5' to 31.5'	BEDROCK GREY GNEISS 100% RECOVERY RQD = 100% 2 PIECES
	28					
	29					
	30					
	31					
				31.5		
	32	R-4	NXM		ADVANCED NXM Double TUBE CORE BARREL 5.0' SAMPLED FROM 31.5' to 36.5'	BEDROCK GREY GNEISS 100% RECOVERY RQD = 90% (5 Pieces) (Quartzite Seams)
	33					
	34					
	35					
	36					
				36.5		
	37				END OF EXPLORATION 9/27/94 BOTTOM OF BORING - 36.5' GRADED BORING w/ CEMENT/BENTONITE GROUT TO TOP OF BEDROCK	

ED FORM 58A (Test)

Boring No. FD-B

FIELD LOG OF TEST BORING

Co-ordinates: N 201265.44 E 44605006

Elevation Top of Boring 453.60 M.S.L. Hammer Wt. _____ Boring Started 9/22/94
Total Overburden Drilled 0 Feet Hammer Drop _____
Elevation Top of Rock 453.60 M.S.L. Casing Left _____ Boring Completed 9/22/94
Total Rock Drilled 19.0 Feet Subsurface Water Data 453.60 Page SEE SEC. 9
Elevation Bottom of Boring 434.60 M.S.L. Obs. Well _____
Total Depth of Boring 19.0 Feet Drilled By Ma. Hawkins, L. Wheeler
Core Recovered 100 % No. Boxes 1 Mfg. Des. Drill CME-45L
Core Recovered 19 Ft.: _____ Diam. _____ In. Inspected By: T. Wiggins
Soil Samples None In. Diam. _____ No. Classification By: T. Wiggins
Soil Samples _____ In. Diam. _____ No. Classification By: _____

DEPTH f's	CORE/SAMPLE			BLOWS PER FT CORE REC'Y	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE	DEPTH RANGE			
1	R-1	NXM	0.0' to 4.0'	98%	NXM DOUBLE TUBE CORE BARREL 0.0'-4.0'	BEDROCK: GREY GNEISS - VERT. SEAMS 48" RUN 47" REC., 3 PIECES R&D = 80%
2						- WEATHERED TO 3.0'
3						- QUARTZITE SEAMS
4	R-2	NXM	4.0' to 9.0'	100%	NXM DOUBLE TUBE CORE BARREL 4.0'-9.0'	BEDROCK: GREY GNEISS - VERT. SEAMS - QUARTZITE SEAMS 60" RUN - 60" REC. 100% RECOVERY 3 PIECES R&D = 100%
5						
6						
7						
8						
9	R-3	NXM	9.0'			BEDROCK:

GENERAL REMARKS:
7.5" WATER (BORING IN THE RIVER)

DEPTH		CORE/SAMPLE		BLOWS PER FT CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
ft.		NO.	SIZE			
11		R-3 Cont'd	NXM		NXM DOUBLE TUBE CORE BARREL 9.0' - 14.0'	BEDROCK: GREY GNEISS - JST. SEAMS 60" RUN - 60" REC. 3 PIECES RQD = 100%
12						
13						
14						
15		R-4	NXM	14.0 19.0	NXM DOUBLE TUBE CORE BARREL 14.0 - 19.0'	BEDROCK GREY GNEISS - QUARTZITE SEAMS 60" RUN - 60" REC. 7 pieces RQD ~ 87%
16						
17						
18						
19					END EXPLORATION 9/22/94 GRADED BORING WITH CEMENT/BENTONITE GROUT TO SURFACE	
20						
21						
22						
23						
24						
25						
26						

11:55

FIELD LOG OF TEST BORING

Co-ordinates: N 201200.91 E 446036.25

Elevation Top of Boring 455.19 M.S.L. Hammer Wt. 300# Boring Started 9/20/94
Total Overburden Drilled 11.0 Feet Hammer Drop 18"
Elevation Top of Rock 444.19 M.S.L. Casing Left NO Boring Completed 9/20/94
Total Rock Drilled 22.0 Feet Subsurface Water Data 455.19 Page SEE SER. 9
Elevation Bottom of Boring 422.19 M.S.L. Obs. Well NO
Total Depth of Boring 33.0 Feet Drilled By MA. HAWKINS, C. WHEELER
Core Recovered 98 % No. Boxes 2 Mfg. Des. Drill CME-45C
Core Recovered 21.5 Ft. : 2 1/8 In. Inspected By: T. WIGGINS
Soil Samples 3" In. Diam. 2 No. Classification By: T. WIGGINS
Soil Samples _____ In. Diam. _____ No. Classification By: _____

DEPTH	CORE/SAMPLE		BLOWS PER FT CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE			
1	S-1		9 0.0 TO 1.0 28 2.0	3" SPOON 300# HAMMER 3" RECOVERY	CMP GRAVEL, COBBLES, TRACE CMP SAND TO 4.0' SATURATED FROM SURFACE
2			42 2.0 TO 4.0 35	14" RECOVERY	
3	S-2		35 28	BROKE SAMPLER 50 BLOWS/0" C 4.0'	BOULDERS, (RIP-RAP) COBBLES, ROCK FRAGMENTS TO 11.0' (BOULDERS TO 20" Ø VOIDS TO 6" THICKNESS)
4				ROLLERBIT TO 5', SPUN NW CASING TO 5'	
5	OB-1	NXM	56%	CORE (OVERBURDEN) FROM 5.0' to 9.5' (NXM)	
6				SPUN NW CASING TO 9.5'	
7					
8					
9				ROLLERBIT BOLDER TO 10.5'	

GENERAL REMARKS:


DEPTH		CORE/SAMPLE			BLOWS PER FT CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	ft.	NO.	SIZE	DEPTH RANGE			
	11	R-1	NXM		83%	ROLLER BIT TO 10.5' ADVANCED NXM DOUBLE TUBE CORE BARREL 30" INTO BEDROCK - SPUN CASING TO 13.5' (NW) SAMPLED FROM 11.0-13.5 NXM CORE	BOULDER, ROCK FRAGMENTS TO 11.0' BEDROCK: 83% REC. GREY GNEISS WEATHERED TO 13.0' RQD = 82% 3 PIECES
	12						
	13						
	14	R-2	NXM		100%	ADVANCED NXM DOUBLE TUBE CORE BARREL 4.5' SAMPLED FROM 13.5-18.0'	100% REC. RQD = 100%, 3 PIECES GREY GNEISS
	15						
	16						
	17						
	18	R-3	NXM		100%	ADVANCED NXM DOUBLE TUBE CORE BARREL 5.0' SAMPLED FROM 18.0-23.0'	100% REC. RQD = 100%, 4 PIECES GREY GNEISS
	19						
	20						
	21						
	22						
	23	R-4	NXM		100%	ADVANCED NXM DOUBLE TUBE CORE BARREL 5.0' SAMPLED FROM 23.0-28.0'	100% REC. RQD = 100%, 6 PIECES GREY GNEISS
	24						
	25						
	26						

NED FORM 58A (Test)


Boring No. FD-D

DEPTH		CORE/SAMPLE			BLOWS PER FT CORE RECVY	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
ft.		NO.	SIZE	DEPTH RANGE			
28		R-5	NXM		100%	ADVANCED NXM DOUBLE TUBE CORE BARREL 5.0' SAMPLED FROM 28.0 - 33.0	100% RECOVERY R&D = 100%, 5 PIECES BEDROCK: GREY GNEISS - QUARTZITE SEAMS - NR. VERTICAL SEAMS
29							
30							
31							
32							
33							
						END EXPLORATION 9/20/94	
						GROUTED BORING WITH CEMENT/BENTONITE GROUT TO SURFACE	

c. Figure 1 - General Project Location Map



VICINITY MAP
N.T.S.



LOCATION MAP

SCALE IN MILE
7.5 0 7.5 15 ML.

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION
CORPS OF ENGINEERS
WALTHAM, MASS.


D.S.S.
DES. BY
D.S.S.
DR. BY
T.L.B.
CK. BY

**TOWNSHEND LAKE
SCOUR HOLE STUDY
LOCATION MAP**


WEST RIVER TOWNSHEND, VT.

GEOTECH. ENG. BR. SCALE: AS SHOWN
SK. NO. 1 DATE:

d. Proposed Boring Locations - Plate No. 1



e. Boring Location Plan



NOTES

1. For details of road and borrow area "A" see Sheet 3.
2. For details of gateway and outlet works see Sheet 7.
3. See Specifications for disposal of power and telephone lines within construction area.

4. See all Borrow Area "A" and Connecting Road excavation.


Record Drawing

Contract No. DA-19-016 CIV ENG 59-103

NO.	DESCRIPTION	DATE
1	Final field work completed	10-10-58
2	Revised field work	11-10-58
3	Revised field work	12-10-58
4	Revised field work	1-11-59
5	Revised field work	2-11-59
6	Revised field work	3-11-59
7	Revised field work	4-11-59
8	Revised field work	5-11-59
9	Revised field work	6-11-59
10	Revised field work	7-11-59

U. S. ARMY ENGINEER DISTRICT, GARRISON Office of Surveying Beverly, Mass.	
CONNECTICUT RIVER FLOOD CONTROL TOWNSHEND DAM GENERAL PLAN	
WEST RIVER, VERMONT	
DESIGNED BY RFP CHECKED BY RFP APPROVED BY RFP	DATE JULY 1958
SCALE 1" = 100'	
CT-1-5304	

PREPARED BY THE GARRISON DISTRICT FOR THE
U. S. ARMY ENGINEER DIVISION, NEW ENGLAND



BORING LOCATION PLAN

DRAWN BY
DHO

SCALE
1" = 30'

PROJECT No.
CD 0047

DATE
9-30-94

TOWNSHEND DAM
TOWNSHEND, VERMONT

ATLANTIC TESTING LABORATORIES, Limited

CANTON, NY
WILLISTON, VT


CICERO, NY
UTICA, NY

ENDICOTT, NY
MANCHESTER, NH

SECTION 9

OTHER RECORDS TAKEN

a. Survey Notes



N201270.807 stake w/ tack?
E446228.662

top of wall
BM Disk
El. 486.38

E446006

"Z" N201249.220
E445956.891
Top of guardrail post


N201200

STA 2+61.26
N201022.858
E446134.508
R.R. spike w/ pin hole


LEGEND

○ EXISTING BORING LOCATION

● PROPOSED BORING LOCATION



DEPARTMENT OF THE ARMY NEW ENGLAND DIVISION CORPS OF ENGINEERS WALTHAM, MASSACHUSETTS	
CONNECTICUT RIVER FLOOD CONTROL	
TOWNSHEND DAM SCOUR HOLE STUDY	
PROPOSED REMEDIAL MEASURES	
DESIGN BY D.S.S.	WEST RIVER, VERMONT
DESIGNED BY T.J.B.	
GEOTECH. ENG. DIV.	SCALE: AS SHOWN
PLATE NO. 3	DATE: JULY 1994



b. Water Table Data

Boring No: ED-A

SUBSURFACE WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below original ground

BORING LOCATION SKETCH

Boring No: 2D-B

SUBSURFACE WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below original ground

BORING LOCATION SKETCH

SUBSURFACE WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below original ground

BORING LOCATION SKETCH

Earing No: FDD

SUBSURFACE WATER OBSERVATIONS

[illegible]

Note: Depths are in feet below original ground

BORING LOCATION SKETCH

c. Rock Coring Data

FIELD LOG OF TEST BORING IN ROCK

SITE Townsend Dam

ROLL NO. FD-A

PAGE 1 of 1

DATE	DEPTH FT.		RUN PT.	RUN REC'V'Y PT.	REC'V'Y %	DRILLING BEHAVIOR			ACTUAL DRILLING TIME	BIT NO. SIZE AND TYPE	ADDITIONAL REMARKS
	FROM	TO				FEED	WATER	REASON FOR PULL			
9/23/94	0	5.0	5.0	3.5	70	med.	Loss of Water	5' Barrel	20 MIN	NXM Dbl. Tubelore Barrel	Overburden Sample OB-1 Cobbles, Boulders
	5.0	8.5	3.5	1.5	43	med	Loss of Water	End of Drill Rig Extension	15 MIN	NXM Dbl. Tubelore Barrel	Overburden Sample OB-2, Cobbles, Boulders
	15.5	20.0	4.5	4.5	100	med	No Loss of Water	5' Barrel	18 MIN	NXM Dbl. Tubelore Barrel	Bedrock, Run 1 Grey Gneiss
	20.0	25.0	5.0	5.0	100	med	No Loss of Water	5' Barrel	15 MIN	NXM Dbl. Tubelore Barrel	Bedrock, Run 2 Grey Gneiss
	25.0	30.0	5.0	5.0	100	med.	No Loss of Water	5' Barrel	15 MIN	NXM Dbl. Tubelore Barrel	Bedrock, Run 3 Grey Gneiss
	30.0	35.0	5.0	5.0	100	med	No Loss of Water	5' Barrel	22 MIN	NXM Dbl. Tubelore Barrel	Bedrock, Run 4 Grey Gneiss

TOTAL BED ROCK DRILLED 19.5 FEET

TOTAL BED ROCK RECOVERED 19.5 FEET

BED ROCK RECOVERY 100 PERCENT

DRILLER M. HAWKINS, C. WHEELER

INSPECTOR T. Wiggins

RED FORM
DEC 63 130

REPLACES FORM OF APR 62 WHICH MAY BE USED UNTIL EXHAUSTED

C-56

FIG NO. 5

FIELD LOG OF TEST BORING IN ROCK

SITE Townshend Dam

ROLL NO. FD-B

PAGE 1 of 1

DATE	DEPTH FT.		R.O.M. PT.	REC'V'T PT.	REC'V'T %	DRILLING BEHAVIOR			ACTUAL DRILLING TIME	BIT NO. SIZE AND TYPE	ADDITIONAL REMARKS
	FROM	TO				FEED	WATER	REASON FOR PULL			
9/26/94	0.0	5.0	5.0	1.4	28%	med.	Loss of Water	5' Barrel	15 min	Nxm Dbl. Core Tubecore Barrel	Overburden OB-1 Cobbles, Boulders
	11.0	16.0	5.0	1.0	20	med.	Loss of Water	5' Barrel	6 min	Nxm Dbl. Tubecore Barrel	Overburden OB-2 Cobbles, Boulders
	16.5	21.5	5.0	4.5	90	med.	No Loss	5' Barrel	20 min	Nxm Dbl. Tubecore Barrel	Run 1, Bedrock Grey GNEISS
9/27/94	21.5	26.5	5.0	5.0	100	med.	No Loss	5' Barrel	15 min	Nxm Dbl. Tubecore Barrel	Run 2, Bedrock Grey GNEISS
	26.5	31.5	5.0	5.0	100	med.	No Loss	5' Barrel	20 min	Nxm Dbl. Tubecore Barrel	Run 3, Bedrock Grey Gneiss
	31.5	36.5	5.0	5.0	100	med.	No Loss	5' Barrel	23 min	Nxm Dbl. Tubecore Barrel	Run 4, Bedrock Grey Gneiss

TOTAL BED ROCK DRILLED 20.0 FEET

TOTAL BED ROCK DISCOVERED 19.5 FEET

BED ROCK RECOVERY 97.5 PERCENT

DRILLER M. Hawkins, C. Wheeler

INSPECTOR A. Brown

RED FORM 100
DEC 63

REPLACES FORM 100 OF APR 63 WHICH MAY BE USED UNTIL EXHAUSTED

C-56

FIG NO. 5

FIELD LOG OF TEST DRILING IN ROCK

SITE Townshend Dam

ROLE NO. FD-C

PAGE

1 of 1

DATE	DEPTH FT.		RUN PT.	RUN REC'V'Y PT.	REC'V'Y %	DRILLING BEHAVIOR			ACTUAL DRILLING TIME	BIT NO. SIZE AND TYPE	ADDITIONAL REMARKS
	FROM	TO				FEED	WATER	REASON FOR STOP			
9/22/94	0.0	4.0	4.0'	3.9'	98	med.	No Loss	DRILLER CONVENIENCE - EVEN ROD LENGTH	12 MIN	NXM Dbl. Tube Core Barrel	Run #1 Weathered Rock to 3.0', Grey GNEISS
	4.0	9.0	5.0	5.0	100	med.	No Loss	5' Barrel	15 MIN	NXM Dbl. Tube Core Barrel	Run #2 Grey GNEISS - Vert. Seams, Quartzite seams
	9.0	14.0	5.0	5.0	100	med.	No Loss	5' Barrel	17 MIN	NXM Dbl. Tube Core Barrel	Run #3 Grey GNEISS Vert. Seams
	14.0	19.0	5.0	5.0	100	med.	No Loss	5' Barrel	15 MIN	NXM Dbl. Tube Core Barrel	Run #4 Grey GNEISS

TOTAL BED ROCK DRILLED 18.190 FEET

TOTAL BED ROCK RECOVERED 18.9 FEET

BED ROCK RECOVERY 99 PERCENT

DRILLER M. Hawkins, C. Wheeler

INSPECTOR T. Wiggins

HEID FORM
DEC 63 130

REPLACES FORM OF APR 63 WHICH MAY BE USED UNTIL EXHAUSTED

C-56

FIG NO. 5

FIELD LOG OF TEST BORING IN ROCK

SITE Townshend Dam

ROLE NO. FD-D

PAGE 1 of 1

DATE	DEPTH FT.		RUN PT.	RUN REC'V'Y PT.	REC'V'Y %	DRILLING BEHAVIOR			ACTUAL DRILLING TIME	BIT NO. SIZE AND TYPE	ADDITIONAL REMARKS
	FROM	TO				FEED	WATER	REASON FOR PULL			
9/20/94	11.0	13.5	2.5	2.1	83	medium	No Water Loss	5' Barrel	15 min	NXM Double Tube Core Barrel	Run #1 Weathered Rock to 13', Grey Gneiss
9/20/94	13.5	18.0	4.5	4.5	100	medium	No Water Loss	5' Barrel	11 min	NXM Double Tube Core Barrel	Run #2 Grey Gneiss
9/20/94	18.0	23.0	5.0	5.0	100	medium	No Water Loss	5' Barrel	15 min	NXM Double Tube Core Barrel	Run #3 Grey Gneiss
9/20/94	23.0	28.0	5.0	5.0	100	medium	No Water Loss	5' Barrel	15 min	NXM Double Tube Core Barrel	Run #4 Grey Gneiss
9/20/94	28.0	33.0	5.0	5.0	100	medium	No Water Loss	5' Barrel	15 min	NXM Double Tube Core Barrel	Run #5 Grey Gneiss Quartzite Seams

TOTAL BED ROCK DRILLED 22 FEET

TOTAL BED ROCK RECOVERED 21.5 FEET

BED ROCK RECOVERY 98 PERCENT

DRILLER M. Hawkins/C. Wheeler

INSPECTOR T. Wiggins

HEID ^{FORM} DEC 63 130

REPLACES EDITION OF APR 63 WHICH MAY BE USED UNTIL EXHAUSTED

C-56

FIG NO. 5

d. Field Log of Test Boring

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site TOWNSEND DAM PROJECT NO. _____
 Hole No. FD-A Diam. (Casing) 3" Page 1 of _____ Pages
 Co-ordinates: N 201255.60 E 446170.20 Boring Started 9/22/94
 Drilled by M. Hawkins, C. Wheeler Boring Completed 9/22/94
 Report Submitted _____

Purpose of Exploration To Define character of subsurface materials in the outlet scour hole

Elevation Top of Hole 460.23 M.S.L. Casing Left in Place 0 Feet
 Total Overburden Drilled 15 Feet
 Elevation Top of Rock 445.23 M.S.L.
 Elevation Bottom of Hole 425.23 M.S.L.
 Total Rock Drilled ~~15.0~~ 20.0 Feet TOTAL RIP-RAP DRILLED 15.0 FEET
 Total Depth of Hole 35.0 Feet
 Core Recovered 100 %
 Core Recovered 19.5 ft.; 2 1/4 in. Diam.
 Soil Samples _____ in. Diam. _____ No.
 Soil Samples _____ in. Diam. _____ No. Water Table Depth 8.8' (induced)

Depth		Method of Drilling and Type of Bit Used	INDEX
From	To		
0	8.5	NXM Double Tube Core Barrel	Ground Water _____ Back of Page _____
0	15.5	NW casing	Boring Location Sketch _____ Back of Page _____
15.5	35.0	NXM Double Tube Core Barrel	Overburden Record _____ Page _____
			Rock Drilling _____ Page _____
			_____ Page _____
			_____ Page _____
			_____ Page _____

Prepared by T. Wiggins Field Data
 Submitted by _____ Lab. Data

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Townshend Dam PROJECT NO. _____
 Hole No. FD-B Diam. (Casing) 3" Page 1 of 1 Pages
 Co-ordinates: N 201220.59 E 446186.35 Boring Started 9/26/94
 Drilled by M. Hawkins, C. Wheeler Boring Completed 9/27/94
 Report Submitted _____

Purpose of Exploration To define character of subsurface materials
in the outlet Scour hole.

Elevation Top of Hole 462.65 M.S.L. Casing Left in Place 0 Feet
 Total Overburden Drilled 16.5 Feet
 Elevation Top of Rock 446.10 M.S.L.
 Elevation Bottom of Hole 426.10 M.S.L.
 Total Rock Drilled 20 Feet TOTAL RIP-RAP DRILLED 16.5 FEET
 Total Depth of Hole 36.5 Feet
 Core Recovered 97.5 %
 Core Recovered 19.5 Ft.: _____ Diam. 2 1/2 In.
 Soil Samples _____ In. Diam. _____ No.
 Soil Samples _____ In. Diam. _____ No. Water Table Depth 6.8' (induced)

Depth		Method of Drilling and Type of Bit Used	INDEX	
From	To			
0	5.0	NxM Double Tube Core Barrel	Ground Water	Back of Page _____
11.0	16.0	NxM Double Tube Core Barrel	Boring Location Sketch	Back of Page _____
16.5	36.5	NxM Double Tube Core Barrel	Overburden Record	Page _____
0	17	NW Casing	Rock Drilling	Page _____
				Page _____
				Page _____
				Page _____

Prepared by A. Brown Field Data
 Submitted by _____ Lab. Data

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site TOWNSEND DAM PROJECT NO. _____
 Hole No. FD-C Diam. (Casing) 3" Page 1 of _____ Pages
 Co-ordinates: N 201565.44 E 446050.06 Boring Started 9/22/94
 Drilled by M. Hawkins, C. Wheeler Boring Completed 9/22/94
 Report Submitted _____

Purpose of Exploration To Define character of subsurface materials in the outlet scour hole

Elevation Top of Hole 453.60 M.S.L. Casing Left in Place 0 Feet
 Total Overburden Drilled 0 Feet
 Elevation Top of Rock 453.60 M.S.L.
 Elevation Bottom of Hole 434.60 M.S.L.
 Total Rock Drilled 19 Feet TOTAL RIP-RAP DRILLED 0 FEET
 Total Depth of Hole 19 Feet
 Core Recovered 99 %
 Core Recovered 18.9 Ft.; 2 1/8 In. Diam.
 Soil Samples None In. Diam. _____ No.
 Soil Samples _____ In. Diam. _____ No. Water Table Depth 0 (in River)

Depth		Method of Drilling and Type of Bit Used	INDEX
From	To		
0	19	NXM Double Tube Core Barrel	Ground Water _____ Back of Page _____
			Boring Location Sketch _____ Back of Page _____
			Overburden Record _____ Page _____
			Rock Drilling _____ Page _____
			_____ Page _____
			_____ Page _____
			_____ Page _____

Prepared by T. Viggins Field Data
 Submitted by _____ Lab. Data

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Townshend Dam PROJECT NO. _____
 Hole No. FD-D Diam. (Casing) 3" Page 1 of _____ Pages
 Co-ordinates: N 201200.91E 446036.25 Boring Started 9/20/94
 Drilled by M. Hawkins, C. Wheeler Boring Completed 9/20/94
 Report Submitted _____

Purpose of Exploration To Define character of Subsurface Materials in the
Seam Hole

Elevation Top of Hole 455.19 M.S.L. Casing Left in Place 0 Feet
 Total Overburden Drilled 11 Feet
 Elevation Top of Rock 444.19 M.S.L.
 Elevation Bottom of Hole 422.19 M.S.L.
 Total Rock Drilled 22' Feet TOTAL RIP-RAP DRILLED 7.0 FEET
 Total Depth of Hole 33' Feet
 Core Recovered 98 %
 Core Recovered 21.5 Ft.: _____ Diam. 2 1/8 In.
 Soil Samples 3" In. Diam. 2 No.
 Soil Samples _____ In. Diam. _____ No. Water Table Depth 0 (in River)

Depth		Method of Drilling and Type of Bit Used	INDEX
From	To		
0	4	3" Diam. Split Spoon	Ground Water _____ Back of Page _____
0	13.5	NW Casing	Boring Location Sketch _____ Back of Page _____
5	33	NXM Double Tube Core Barrel	Overburden Record _____ Page _____
			Rock Drilling _____ Page _____
			_____ Page _____
			_____ Page _____
			_____ Page _____

Prepared by T. Wiggins Field Data
 Submitted by _____ Lab. Data